

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/15/2021-22 Dated: 15-12-2021

APPROVED TENDER SCHEDULE - 'B'

Item 09


Work :- Improvements to roads and Drains at 8th A Main Attur Layout and Surrounding areas in Ward no 03 Attur Yelahanka Satellite Town Sub Division.


Sl No	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri G MAHENDRA (SREE MANOJAVA ENTERPRISES)	
				Rate	Rate in Words
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	244.71	116.17	One Hundred Sixteen Paise Seventeen Only
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	40.79	3776.38	Three Thousand Seven Hundred SeventySix Paise ThirtyEight Only
3	Providing TMT Bars Fe 500 steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification.	Tonne	5.00	63415.22	SixtyThree Thousand Four Hundred Fifteen Paise TwentyTwo Only
4	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centring shuttering cost of material HOM of machinery curing etc., complete excluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification.	Cum	78.11	4350.04	Four Thousand Three Hundred Fifty Paise Four Only

Handwritten signature

Handwritten signature
Executive Engineer,
Yelahanka Division,
B.B.M.P. Bangalore - 64.

Providing and Fixing Pre cast covering Slab 100mm thick made out of CC, jelly 20mm Down size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete. As per Engineer incharge.	Sqm	160.20	2088.34	Two Thousand EightyEight Paise ThirtyFour Only
Providing and fixing RCC precast cover slab of 230mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	28.32	4240.00	Four Thousand Two Hundred Fourty Only


Signature of the Contractor


Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.